

Zestawienie robót ziemnych elementów konstrukcji drogi

Nazwa	km	km	Powierzchnia	Wykop	Nasyp	Wartość netto
			m <sup>2</sup>	m <sup>3</sup>	m <sup>3</sup>	m <sup>3</sup>
30 droga cz 2	2+ 109.10	2+ 522.07	4 510.75	357.00	1 491.69	-1 134.69
31 parking S			268.11	0.00	181.13	-181.13
32 zjazd X			407.26	28.88	55.21	-26.33
33 zjazd X (1)			410.90	19.19	91.97	-72.78
34 zjazd 38			246.50	58.17	8.30	49.87
35 zjazd 19			231.11	26.55	45.10	-18.55
36 PZ1			1 549.22	90.57	446.83	-356.26
37 droga cz 3	2+ 586.43	2+ 790.41	2 146.33	149.69	569.41	-419.72
38 zjazd 39			206.11	11.61	26.13	-14.52
39 zjazd 21			191.20	2.89	49.53	-46.64
40 składnica 3			617.72	8.36	248.56	-240.20
41 PZ2			758.05	15.20	321.70	-306.50
42 droga cz 4	2+ 823.89	3+ 587.51	7 341.59	728.37	333.06	395.31
43 zjazd LT1			200.52	67.78	1.80	65.98
44 zjazd LT2			193.93	67.86	2.39	65.47
45 Zjazd XIII			343.31	22.88	8.65	14.23
46 zjazd XIV			356.09	3.09	24.13	-21.04
47 zjazd 23			173.90	18.88	2.35	16.53
48 zjazd 25			214.81	25.43	3.77	21.66
49 zjazd 26			204.88	25.75	2.44	23.31
50 zjazd 27			178.08	11.89	3.37	8.52
51 składnica 4			1 345.98	217.82	67.38	150.44
52 PZ 3			1 071.99	148.86	106.09	42.77
<b>SUMA</b>			<b>23 168.34</b>	<b>2 106.72</b>	<b>4 090.99</b>	<b>-1 984.27</b>
Suma wykopy						
Wykopy do wykorzystania na miejscu				2 106.72		
Wykopy do wywiezienia				0.00		
Nasyp z wykopu					2 106.72	
Nasyp do dowiezienia					1 984.27	