

Tab. 1.1 - Tabela robót ziemnych

BILANS ROBÓT ZIEMNYCH - DP_1327B							
Pikietą	Pow. wykopu	Pow. nasypu	Obj. wykopu	Obj. nasypu	Catk. obj. wykopu	Catk. obj. nasypu	Obj. netto
0+000.0	0.0	0.0	0.0	0.00	0.00	0.00	0.00
0+008.8	4.0	0.7	17.6	2.94	17.55	2.94	14.61
0+018.9	4.5	0.4	42.7	5.54	60.20	8.48	51.72
0+047.0	4.4	0.3	125.2	9.82	185.39	18.30	167.09
0+074.9	3.6	0.3	111.3	7.19	296.64	25.49	271.15
0+101.7	3.4	0.4	93.5	8.62	390.13	34.12	356.02
0+130.7	1.9	2.7	76.2	45.39	466.35	79.50	386.85
0+156.9	0.5	3.4	30.6	80.06	496.96	159.56	337.40
0+184.7	0.9	2.9	19.6	87.01	516.55	246.57	269.98
0+211.1	1.3	3.3	28.9	81.03	545.41	327.60	217.80
0+240.3	0.7	2.5	28.8	76.56	574.25	404.16	170.09
0+249.2	0.9	2.0	6.8	19.63	581.05	423.79	157.26
0+276.0	1.5	1.5	32.5	47.04	613.52	470.83	142.69
0+303.7	0.8	2.6	31.9	56.83	645.43	527.66	117.77
0+328.9	1.2	8.4	24.8	138.07	670.21	665.73	4.48
0+357.3	0.7	10.4	26.6	266.83	696.80	932.56	-235.76
0+381.6	0.8	3.4	18.3	167.38	715.12	1099.94	-384.82
0+408.8	2.4	0.7	44.6	54.63	759.71	1154.57	-394.87
0+436.5	3.6	0.5	83.9	15.32	843.56	1169.90	-326.34
0+464.8	2.1	1.0	81.1	20.98	924.65	1190.87	-266.22
0+496.4	1.6	1.3	59.8	37.00	984.44	1227.87	-243.43
0+521.2	0.3	3.5	23.6	59.95	1008.09	1287.82	-279.73
0+546.5	1.1	2.9	16.8	81.55	1024.89	1369.37	-344.48
0+572.4	1.5	2.5	32.6	70.54	1057.52	1439.91	-382.39
0+596.5	1.2	3.4	32.2	70.80	1089.76	1510.71	-420.94
0+622.7	0.2	3.3	18.9	86.69	1108.62	1597.40	-488.78
0+645.9	0.6	2.8	9.9	69.99	1118.54	1667.39	-548.85
0+680.6	0.9	3.1	30.5	102.06	1149.02	1769.45	-620.43
0+705.8	0.6	3.2	21.5	78.93	1170.49	1848.38	-677.89
0+729.7	0.5	3.5	13.7	80.73	1184.20	1929.11	-744.91
0+752.4	1.8	1.7	26.5	59.16	1210.72	1988.27	-777.55
0+776.3	2.3	1.2	49.0	34.94	1259.74	2023.21	-763.46
0+800.2	2.3	1.8	55.2	36.70	1314.96	2059.91	-744.94
0+822.5	2.7	1.7	55.4	39.23	1370.41	2099.14	-728.73
0+843.8	3.0	2.0	59.9	38.89	1430.27	2138.03	-707.76
0+867.9	1.6	1.9	55.1	46.04	1485.36	2184.06	-698.71
0+893.3	1.9	1.4	44.6	41.16	1529.94	2225.22	-695.28
0+916.3	1.7	1.7	42.0	35.10	1571.91	2260.32	-688.41
0+936.1	1.9	1.6	35.8	32.90	1607.72	2293.22	-685.50
0+959.7	1.6	1.8	41.4	40.27	1649.10	2333.49	-684.39
0+982.9	1.4	2.3	34.8	47.31	1683.90	2380.79	-696.89
1+006.0	2.0	1.9	39.3	49.20	1723.16	2430.00	-706.84
1+029.2	2.5	1.6	51.8	40.43	1774.95	2470.43	-695.48
1+052.3	2.0	2.1	50.9	41.85	1825.86	2512.27	-686.42
1+074.6	1.8	1.6	41.7	40.90	1867.52	2553.18	-685.66
1+097.1	1.5	2.3	36.5	44.25	1904.00	2597.42	-693.42
1+122.1	1.2	4.8	33.5	88.42	1937.48	2685.85	-748.36
1+147.9	1.5	2.6	34.6	94.62	1972.05	2780.46	-808.42
1+172.1	1.3	2.4	33.1	59.64	2005.18	2840.10	-834.92
1+196.8	0.7	2.7	24.8	61.89	2029.99	2901.99	-872.00