

BILANS ROBÓT ZIEMNYCH – Linia trasowania							
Pikietaż	Pow. wykopu	Pow. nasypu	Obj. wykopu	Obj. nasypu	Całk. obj. wykopu	Całk. obj. nasypu	Obj. netto
1+080.00	0.81	0.22	106.43	16.42	2456.65	300.75	2155.90
1+120.00	0.73	0.25	30.80	9.36	2487.45	310.11	2177.34
1+160.00	0.69	0.24	28.38	9.79	2515.84	319.91	2195.93
1+200.00	0.89	0.19	31.55	8.49	2547.38	328.40	2218.99
1+280.00	1.86	0.22	109.90	16.35	2657.29	344.74	2312.54
1+320.00	0.85	0.20	54.15	8.42	2711.44	353.16	2358.27
1+360.00	0.88	0.18	34.51	7.66	2745.95	360.82	2385.13
1+400.00	0.73	0.18	32.08	7.22	2778.03	368.04	2409.99
1+430.00	1.12	0.06	27.67	3.58	2805.69	371.62	2434.07
1+480.00	0.86	0.36	49.41	10.62	2855.11	382.24	2472.87
1+520.00	1.29	0.32	43.05	13.59	2898.16	395.83	2502.33
1+560.00	1.30	0.34	51.81	13.14	2949.97	408.97	2541.00
1+600.00	3.09	0.11	87.78	8.95	3037.76	417.92	2619.84
1+640.00	2.85	0.11	118.79	4.33	3156.55	422.25	2734.31
1+680.00	2.83	0.10	113.54	4.15	3270.10	426.40	2843.70
1+720.00	2.73	0.11	111.24	4.08	3381.34	430.48	2950.86
1+721.00	2.76	0.11	2.74	0.11	3384.08	430.58	2953.50