

Tabela robót ziemnych										
łącznica WC									Tabela 2.1	
PIKIETAŻ	POWIERZCHNIA		OBJĘTOŚCI			ZUŻYCIE NA MIEJSCU	NADMIAR OBJ,		SUMA	
	WYKOP	NASYP	ODL,	WYKOP	NASYP		WYKOP	NASYP	+	-
km	m ²	m ²	m	m ³	m ³	m ³	m ³	m ³	m ³	m ³
RONDO									0,00	0,00
0+020,00	4,10	129,70	0,00	0,00	0,00	0,00	0,00	0,00		0,00
0+024,00	4,10	129,70	4,00	16,40	518,80	16,40	0,00	-502,40		-502,40
0+050,00	5,00	76,10	26,00	118,30	2675,40	118,30	0,00	-2557,10		-3059,50
0+075,00	2,00	54,30	25,00	87,50	1630,00	87,50	0,00	-1542,50		-4602,00
0+100,00	0,90	42,20	25,00	36,25	1206,25	36,25	0,00	-1170,00		-5772,00
0+120,00	0,90	37,70	20,00	18,00	799,00	18,00	0,00	-781,00		-6553,00
0+140,00	1,00	25,20	20,00	19,00	629,00	19,00	0,00	-610,00		-7163,00
0+152,00	1,20	23,70	12,00	13,20	293,40	13,20	0,00	-280,20		-7443,20
0+166,00	1,20	25,70	14,00	16,80	345,80	16,80	0,00	-329,00		-7772,20
0+182,00	1,20	25,70	16,00	19,20	411,20	19,20	0,00	-392,00		-8164,20
SUMA			344,65	8508,85	344,65	0,00	-8164,20			

KM	WYK	NAS
RONDO		
20	4,10	129,70
24,00	4,10	129,70
50,00	5,00	76,10
75	2,00	54,30
100,00	0,90	42,20
120,00	0,90	37,70
140	1,00	25,20
152,00	1,20	23,70
166,00	1,20	25,70
182,00	1,20	25,70

		WYKOP	NASYP
+10%	SUMA	379,12	9359,74