

Tabela robót ziemnych										
dodatkowa jezdnia 1									Tabela 2.1	
PIKIETAŻ	POWIERZCHNIA		OBJĘTOŚCI			ZUŻYCIE NA MIEJSCU	NADMIAR OBJ,		SUMA	
	WYKOP	NASYP	ODL,	WYKOP	NASYP		WYKOP	NASYP	+	-
km	m <sup>2</sup>	m <sup>2</sup>	m	m <sup>3</sup>	m <sup>3</sup>	m <sup>3</sup>	m <sup>3</sup>	m <sup>3</sup>	m <sup>3</sup>	m <sup>3</sup>
0+110,90	1,50	4,80	14,10	31,02	90,24	31,02	0,00	-59,22	0,00	0,00
0+125,00	2,90	8,00								-59,22
0+136,83	3,00	7,50	11,83	34,90	91,68	34,90	0,00	-56,78		-116,00
0+150,00	2,90	6,70	13,17	38,85	93,51	38,85	0,00	-54,66		-170,66
0+176,86	2,90	6,20	26,86	77,89	173,25	77,89	0,00	-95,35		-266,01
0+186,86	2,30	4,50	10,00	26,00	53,50	26,00	0,00	-27,50		-293,51
			SUMA	208,66	502,18	208,66	0,00	-293,51		

KM	WYK	NAS
110,9	1,50	4,80
125	2,90	8,00
136,83	3,00	7,50
150	2,90	6,70
176,86	2,90	6,20
186,86	2,30	4,50

		WYKOP	NASYP
+10%	SUMA	229,53	552,39